

The Complete Building Service

Tel No 01225 334105
Mobile 07958 626961

**N k J Foster
66 High Street
Bath
BA2 1DD**

Julian Carpenter

27th May 2021

Quotation

Dear Sir,

Please find costs as follows

For works as per spec/plan, after site visit

Set up safety barriers/signs

1

All works with hoggin-posts etc
Wate to tip
Supply all Labour Plant and Materials

The sum of £ 6,744.00 plus VAT

2

As above remove hoggin
Add base tarmac/buff tarmac

The sum of £ 9,231.00 plus VAT

A saving of £647.00 without posts

Includes £500.00 to supply/fit bench

NkJ FOSTER

GREEN TREES SURFACING LTD

Court Farm, Siston, Mangotsfield, Bristol. BS16 9LU

Telephone: 0117 937 4447 Fax: 0117 303 9299

E-mail: mail@greentrees.info Website: www.greentreessurfacing.co.uk

TO:	Julian Carpenter	COMPANY:	Freshford Parish Council
E-MAIL:	jcarps@live.co.uk parish.council@freshfordvillage.com	PAGES:	2
PHONE:	07881 201 955	DATE:	28 th June 2021
REF:	Freshford Village Bus Stop, Freshford Lane, Freshford, Bath BA2 7UR Quotation Number 10287	FROM:	<i>Joe Marshall</i>

Dear Mr Carpenter

Thank you for inviting us to tender for work at the above address. Please find below details of our quotation for your consideration, together with a copy of our terms and conditions.

Quotation is based on suitable access for plant and vehicles and assumes limestone aggregate.

Unless stated otherwise, this is not a fixed price quotation and is subject to re-measure upon

completion. All prices are plus VAT at the prevailing rate.

Excavation of grass verge and installation of new drop kerb:

- It is the responsibility of the homeowner to apply to Bath & North East Somerset Council for the excavation licence.
- Instruct Bath & North East Somerset Council of the date(s) to carry out the works.
- To attend site at Freshford Village Bus Stop, Freshford Lane.
- Erect Highways Chapter 8 signage and barriers to conform to Bath & North East Somerset Council specification.
- To mechanically excavate existing grass verge and 4no. existing road kerbs, forming a new footpath gradient.
- Remove all waste, created by excavation away from site to contractor tip.
- Supply and install 4 linear meters of concrete path edging set in semi dry concrete foundations to create new edging demarcations.
- To supply and install 3no. 150mm x 125mm bull-nose kerbs and 1no. left-hand splay, all set in concrete foundations.
- Supply and lay new weed protector geotextile terram to the base of the excavation.
- Re-instate grass verge area 3.8m (long) X 4.0m (wide) equalling 15.20m² to council specification of 150mm of compacted type 1 stone, 60mm depth of 20mm dense binder course and 20mm depth of compacted hoggin surface course.
- Leave site, clean, tidy and ready for use on completion.
- Inform Bath & North East Somerset of the completed installation works.

For the price of: £2,953.24 + VAT

PLEASE NOTE

When carrying out the works, if our vehicles are required to pass through the new Bath Clean Air Zone, these costs will be charged to the customer in addition to the above quotation.

If there is any further information you require at this stage, please do not hesitate to contact me at the above address.

Regards,

Joe Marshall

Joe Marshall
Green Trees Surfacing Ltd